

New England Overland
Floor Specialist

Ledyard High School Auditorium Stage Renovation

Bid # 22-2

REQUEST FOR PROPOSAL FOR
PERFORMANCE SOUND SYSTEM
THEATRICAL LIGHTING SYSTEM
STAGE CURTAINS ALTERNATE #1
STAGE FLOOR REPLACEMENT ALTERNATE #2,3,4,5
FOR

Ledyard High School
24 Gallup Hill Rd
Ledyard, Ct

2/25/2022

Ledyard Public Schools will accept sealed bids from qualified parties to supply and install flooring, curtains, audio/video equipment, and stage lighting for the Ledyard High School auditorium.

The project is expected to begin installation in the summer of 2022 and be completed prior to August 31, 2022.

A mandatory walkthrough of the project school will take place on March 14, 2022 at 2:00 pm at:

Ledyard High School,
24 Gallup Hill Rd.
Ledyard CT, 06339.

Bid packages can be obtained by emailing Wayne Donaldson, Ledyard Public Schools Facilities Director, at Wdonaldson@ledyard.net. Sealed bid submissions are due on March 31, 2022 by 11 am. Bids must be received at the following address before the assigned date and time.

Ledyard Public Schools
Attn: Wayne Donaldson
4 Blonders Blvd.
Ledyard, CT, 06339

Bids submitted after the deadline will not be considered. Please enclose your bid in a sealed envelope clearly marked with the bid number and name. Questions can be emailed to wdonaldson@ledyard.net until 3 PM on March 28, 2022.

(All questions must be in writing or in an email addressed only to the Director of Facilities)

Ledyard Public Schools reserves the right to waive minor discrepancies in bids; or to accept or reject all or part of any submission. All bid submissions are the property of Ledyard Public Schools and will not be returned to the bidder. Award notification to the successful bidder is expected on or before April 5, 2022

It is strongly urged that all prospective bidders notify Wayne Donaldson, Ledyard Public School Facilities Director, of their interest to ensure receipt of any addendums. Bid packages are available on the Ledyard Board of Education web site www.ledyard.net (listed under district/finance/bids), The Town of Ledyard Website at www.ledyardct.org (listed under Finance), and the State of Connecticut DAS site. The response to all questions will be sent to all firms that have requested bid packages, registered with the Facilities Director, or attended the walk through.

(Downloading the bid from the BoE website will not ensure receipt of any addendums)

All bids must contain a certification stating that the bid amount is valid for a period of 90 days from bid opening date. The successful bidder will be required to provide a certificate of insurance and proof of manufacturers certification for the equipment being offered and any applicable State of Connecticut licenses for the work being performed. All bids must clearly state the equipment warranty information and the successful firm will supply a warranty on labor for a period of two years from the date of completion to cover installation issues or service under the length of the manufacturer's warranty.

BIDDER QUALIFICATIONS

- Each bidder electing to bid shall be a company that maintains fabrication and technical services for production, installation, modification, continued contract maintenance, repair and operator training for professional sound /lighting system installations.
- Each bidder shall submit a completed reference list with their bid. These references shall be of other high-quality professional sound/lighting system installations completed by the bidder of equal complexity.
- Throughout the specified types of equipment installation and procedures there shall be skilled technicians, qualified in the appropriate areas. Personnel scheduled to work on this project must have 5 years or more experience in theatrical sound /lighting installations.
- The contractor must have the ability and prior experience to perform verification tests and initial adjustments prior to acceptance testing, participate in acceptance testing and perform final adjustments and calibrations as required with the consultant.
- Audio system programming shall be performed by a factory certified BSS London Architect programmer.
- The makes and models of equipment were selected to meet the usage of the room and the budget set for the project. Design deviations or substitutions are not permitted.

2.1) SCOPE OF WORK

Performance Audio System

- Suspension and installation of hanging speakers using certified fly ware from building structure from ceiling on stage left/right/center.
- Establish all wire/pipe routes, chases, openings etc., for all needed cabling
- Supply and installation of all microphone/speaker/ line level audio cables,
- Construct and pre-wire equipment racks.
- Install input/output custom jack plates on stage proscenium walls F. Provide all needed conduit for any exposed low voltage cabling as required by code.
- Fully program and adjust digital signal processors and wall mounted presentation controller for multi-use pre-sets.
- Wall mounted touch screen will have to following functions:
 - activate hot mics 1, with independent volume control of each

- turn on/off video projector and raise/lower projection screen
- activate Bluetooth with volume control
- volume control of video source
- Provide all high voltage electrical needed for the new audio system.
- Remove and discard all old audio equipment
 - Remove the old wall mounted PA system and provide a custom metal wall plate to cover the opening in the wall.
 - Provide a fully functioning and operational sound system as described in the equipment listed below.
- Provide a final “Working London architect design file” for the DSP processors.
- Obtain all needed permits.
- Install dedicated Wi-Fi network for iPad control of mixer
- Configure the system so the on-stage hot mics and Bluetooth audio are controlled via the wall mounted controller for a standalone presentation system.
- Provide full system programming and setup plus allow for 4 hours of end user training on the sound system proper use and care.

2.2) AUDIO EQUIPMENT LIST

SPEAKERS

- 9 JBL mini line array full range vrx-932la-white
- 3 JBL mini line array subwoofer vrx- 915s- white
- 2 JBL full range hanging stage speakers ac266/99 black
 - These speakers are hung from first electric for stage coverage
- JBL dual 8” full range under balcony speakers ac28/26 2 JBL array frames vrx-smaf 2 ATM swivel beams sb-18
- 2 JBL floor monitors prx412m
- BSS digital signal processor blu 160 8x8
- 1 AMX touch screen md1002
- 1 AMX system controller nx2200
- 3 Crown quad channel power amplifiers for mains dci 4/1250
- 4 Crown dual channel power amplifier dci 4/600

ELECTRONICS

VIDEO INFRASTRUCTURE

- 1 Kramer video mixer vs611dt
- 1 Kramer receiver for projector tp780rxr
- 3 Kramer HDMI transmitters stage l/r , booth wp211t
- 3 Kramer HDMI receivers tp789r

FRONT END

- 1 Behringer digital mixing console x32
- 1 Switchcraft Bluetooth 318bt
- 1 Apple Ipad 10" gen 8 or better

MICROPHONES

- 5 AKG overhead stage microphones chm99b
- 12 AKG handheld wireless systems wms470 vocal set c5
- 12 AKG beltpacks pt470
- 12 AKG lapel elements c417pp
- 8 AKG wired vocal microphones d7
- 8 AKG wired instrument microphones d40
- 3 AKG antenna distributors aps4
- 2 8" x8" input plates stage left/stage right
- 8 female XLR labeled 1 thru 8
- Decora cutout for Kramer transmitter
- Mount 18" off stage left/right proscenium wall
- 3 three gang input/output plates
- SL plate 1 -fxlr hot mic #1
- 1- f speak on mon #1
- 1 female rj45 for digital snake SR plate
- 1 -fxlr hot mic #2

WALL PLATES

- 1- f speakon mon #2
- 1 female rj45 for digital snake
- Mount 18" off stage right and stage left proscenium walls
- Pit plate 2 speakon mon #1,mon #2
- 1 female rj45 for digital snake

- Mount center stage orchestra pit

SUPPORT EQUIPMENT

- 1 HSA custom locking roll top desk for audio mixer extract-ii
- 2 Behringer digital snake box s16
- 1 road case for digital snake with front/back doors 2 space
- 1 Middle Atlantic portable rack on caster for wireless system ptrk 2726
- 2 Middle Atlantic rack drawers for portable wireless rack UD3
- 1 Middle Atlantic floor rack for booth equipment erk-3520
- 1 Middle Atlantic locking front door vfd-3d
- 2 Whirlwind duracat cable for digital snake box enc6sr-010
- 2 Hotwires speakon monitor cables sp14/25s
- 12 Hot wires microphone cables mc12-25
- 12 on-stage stands round base microphone stands ms7201b
- 12 on-stage boom arms msa7040tb
 - All needed 12/2 speaker cable
 - All needed signal cable, data cable, microphone cable
- 3 JBL yoke brackets for under balcony speakers mtu28
- 2 JBL yoke brackets for flown stage monitors mtu 266/99
- 1 Da-lite low voltage controller for projection screen control 99622
- All needed flyware, man lifts, electrical, pathways ect to provide a fully functioning system

3.1 THEATRICAL LIGHTING SYSTEM

SCOPE OF WORK

- Remove the following existing
 - Strip lights and recycle
 - remove existing stage electrics and power boxes
 - remove TTI dimmer and house light control
 - remove conduit and circuits to dimmer rack
 - remove small FOH pipe and temporary cabling
 - remove 5 existing entry stations
- re-route feeds and circuits to new wall mounted junction boxes
- install feed for new DRd rack, mezzanine level
- install DRd rack for house lighting, mezzanine level
- Terminate existing house light circuits in DRd rack.

- Install new conduit for (4) stage electrics to new grid iron junction boxes.
- Install connector strips on new rigging assemblies and positions
- Install flex connection to connector strip, install new wire and terminate.
- Re-use main FOH pipe, rigging, connector strip and existing circuit wiring.
- Install 4 outlet boxes on wall, install conduit from rack (DR, UR, UL, DL)
- Install equipment rack , mezzanine level stage left
- Install network cabling to 4 stage electrics, 1- FOH, 4- wall stage boxes (DR,UR, UL ,DL)
- Install new touch screen stations in booth and stage left
- Install new entry stations
- Install 48- 4' LED tubes in existing work light fixtures on stage
- Prepare, hang, cable, configure, and address new LED stage lighting fixtures.
- Install lighting console in booth
- Provide console patch, create site specific magic sheet
- Provide all high voltage and low voltage electrical labor and materials
- Provide system integration, commissioning, programming, and system training (4 hours)

3.2) THEATRICAL LIGHTING EQUIPMENT LIST

- ETC lighting control console Element 2 1k w/ 1024 outputs, dust cover, two active display port to DVI adaptors, keyboard, mouse, mousepad, furman ss6b surge strip, locking power cord,
- LED little lite
- Dell 23.8" touch console monitors color black p2418ht 1- CBI net m/m rj45 extension cable 25' 7- ETC RSN-DMX1-0-p-4 response)
- port portable touring gateway w/ (1) XLR-d5f, c-clamp and safety cable
- ETC RSN-DMX2-0-p-4 response (2) port portable touring gateway w/ (1) xlr-d5f, c-clamp and safety cable
- 7- ETC ecpb net network plug-in station
- 7-ETC ecpb pb1 1-gang 2.5" deep back box, surface mount
- 7-CBI net m/m rj45 extension cable 25'

POWER SYSTEM

- 1-ETC DRd6-12-120 dimming enclosure

- 1-ETC p-DRd-tk paradigm termination kit
- 1-ETC p-acp3 paradigm architectural control processor 1-ETC p-spm-e paradigm station power module
- 12-ETC d20 dual 20 amp dimmer module
- 13-ETC r20 dual 20 amp relay module
- 2-ETC cc20 dual 20 amp constant module

ARCHITECTURAL CONTROL

- 5-ETC uh10005-s4 preset station w/ 4 presets and off buttons, surface mount
- 5-ETC Lbb1 single gang surface mount back box
- 5-ETC slc-1b unison 1 gang sliding locking cover
- ETC p-ts7-4 paradigm LCD touch screen, surface mount
- 1-ETC p-lcd-sbb lcd locking surface mount back box
- 1-ETC p-lcd-lc4 wall mount locking cover
- Network control equipment rack
 - 1-lowell 12 space rack with locking front door
 - 1-furman m8x2
 - 1-C2g 24 port cat6 patch panel
 - Lowell cbp-1 cable pass through w/ brush strip
 - 1-netgear fs728tp-100nas prosafe 24 port smart switch w/poe and 4-sfp ports
 - 24-cable matters cat6 patch cables 2'
 - 1-lowell udel-314
 - Tripp lite smartpro ups

ELECTRICAL DISTRIBUTION

- 4-SSRC sm-3-2pgfl-1-520d surface mount outlets boxes w/ 2-2p&g flush mount connectors, on 1-20amp circuit
- 1-SSRC bal-40-6/12-2pgpt-4/8-1520pt-1 net connector strip 40' w/ 12- 18" 2p&g pigtails, on 6- 20 amp circuits, 8-18" Edison pigtails on 4- 20 amp circuits, 1 net rj45 and double pipe mounting hardware
- 3-SSRC bal-40-12/12-2pgpt-4/8-1520pt-1-net connector strip 40' w/12-18" 2p&g pigtails on 12-20 amp circuits, 1- netrj45 and double pipe mounting hardware 4-schedule
- 40 1.5" sleeved painted black baton pipe @42'
- 12-leviton 5266-b 5-15 Edison plug
- 48- LED tubes 48" t8 16 watt daylight

STAGE LIGHT FIXTURES & ACCESSORIES

- 26-ETC csspots-a
- 26-ETC 400lt lens tubes degree TBD
- 15-ETC cspar-a
- 15-ETC selow 7.5 cspar
- 6-ETC cyc-a
- 50-CBI dmx m/f 5pin 10' ext cable
- 25-CBI Powercon-powercon jumper 10'
- 6-CBI xlr 5 pin terminator
- 1-HAS locking roll top desk for lighting console and monitors extrt-ii modified as needed to fit gear.

4.1) Alternate # 1 Stage Curtain Replacement

Scope of work

- a) Removal and disposal of main traveler curtain, main valance, boarders, legs, US traveler
- b) Inspect traveler curtain tracks, vertical pulleys and ropes. Repair/replace as needed
- c) Remove existing drapery rigging points
- d) Install all new drapery rigging points and pipe
- e) Install all new fabric as listed

Curtain Equipment list

1-Main valance of IFR 25oz Prestige 4' x 40', lined with celtic cloth, 50% fullness, top hem

2-Main traveler of IFR 25oz Prestige 18' x 25', lined with celtic cloth. 50% fullness, snaphooks, top amnd side hems, weighted bottom, ½ width faceback

4-Boarders of IFR 23oz drama 4' x 40' , unlined, 50% fullness, 8-Legs of 23oz drama 18' x 10', unlined , 50% fullness

2-US Traveler of 23oz drama, unlined, 50% fullness, snaphooks, ½ width faceback

1-Cyclorama of IFR muslin 16' x 48', white, seamless, unlined, 0% fullness, 2" double turned, top,side hemed, bottom weighted

2-iWeiss r205 3/8" sash cord@ 125'

Drapery rigging equipment

13- schedual 40 1.5" black batten pipe @ 42'

97- adjustable beam clamps rigging points w/ ¼" grade 3- proof chain @10', center point beam clamp, ½" shoulder eyebolts, 2- chackles, 1-iWeiss p305 pipe clamp

Drapery Track

2-iWeiss align series channel bi-parting track, CWANA @ 52'

1-iWeiss align series channel walk along track CWANA @ 50'

8-iWeiss align series channel walk along track CWANA @ 10'

Page nine

Alternate # 2

2-Lycian ZOT 350 LED follow spot fixtures

Alternate # 3

4-Chauvet moving fixtures maverick force 2 profile

4-CBI DMX m/f 5 pin ext cable @ 10'

All needed omega brackets, couplers, safety cables, Powercon

cables Alternate #4

1- ETCPAD portable access devise, ETCpad USB hub

Alternate #5

Removal and replacement of entire stage hardwood flooring, new floor and stairs

to be stained black and sealed 3 times with matt finish sealer. Please provide pricing on the final floor finish to be Rose Brand Stage flooring. Quote Dura Teatro and Glide.

Note: This is a turn Key project, all services needed to provide the school with a 100% functioning audio/theatrical lighting system as depicted in the above pages should be included in vendors pricing.

Makes and model listed were chosen based on the projects budget and needs. Design/functionality deviations will not be permitted.

REFERENCES

List below all requested information for at least five projects. Projects are to be similar in scope of work and contract amount to this project. This reference list must be completed and returned with the Bid proposal.

1. Project Name (or description) Manchester High School Contract Amount 312,000.00 Completion Date September 2021
Owner Manchester Public Schools
Contact Name Lindsey Boutillier Telephone 860-268-1466
Architect/Consultant _____
Contact Name _____ Telephone _____

2. Project Name (or description) Stratford High School Contract Amount 95,000.00 Completion Date October 2020
Owner Stratford Public Schools
Contact Name Mike Barbaro Telephone 203-284-1856
Architect/Consultant _____
Contact Name _____ Telephone _____

3. Project Name (or
description)

Amount 45,000.00 Completion Date August 2018 Contract New Canaan High School

Owner

New Canaan Public Schools

Contact Name Jay Egan Telephone 203-979-0762

Architect/Consultant

Contact Name _____ Telephone _____

4.

Project Name (or
description) Old Lyme/Region 18 Contract July 2021

Amount 37,768.00 Completion Date July 2021

Owner

Old Lyme Public Schools

Contact Name Ron Turner Telephone 860-334-3889

Architect/Consultant

Contact Name _____ Telephone _____

Page eleven

Auditorium Sound, Theatrical lighting system completely installed

For the lump sum of _____
Written in words

\$ _____
Written in figures

Alternate #1 Stage Curtain supplied and completely installed

For the lump sum of _____
Written in words

\$ _____
Written in figures

Alternate # 2 followspot fixtures

For the lump sum of _____
Written in words

\$ _____
Written in Figures

Alternate # 3 Moving yoke fixtures

For the lump sum of _____

Written in words

\$ _____

Written in Figures

Alternate #4 wireless control of lighting

For the lump sum of _____

Written in words

\$ _____

Written in Figures

Page twelve

Alternate #5 Stage floor replacement

For the sum of _____ Eighty Six Thousand Four Hundred Fifty Dollars

Written in words

\$ _____ \$86,450.00

Written in Figures

A. Rose Brand Flooring Dura

For the sum of _____ One Hundred Two Thousand Three Hundred Forty Two Dollars

Written in words

\$ _____ \$102,342.00

Written in Figures

B. Rose Brand Flooring Teatro

For the sum of _____ One Hundred Three Thousand One Hundred Thirty Eight Dollars

Written in words

\$ _____ \$103,138.00

Written in Figures

C. Rose Brand Flooring Glide

For the sum of One Hundred Three Thousand Four Hundred Seven Dollars
Written in words


\$ \$103,407.00
Written in Figures

New England Overland Floor Specialists
112 Nod Rd Unit 7
Clinton, CT 06413
williamsdax@rocketmail.com
203-401-1239

Dax Williams - Director



Quote Valid for 90 days after Bid Opening



MARCH 26, 2022

**FROM: CT. STAGE AND MOVIE SUPPLY INC.
459 EAST STREET
PLAINVILLE, CT 06062
860-747-1232
860-747-2448
ctstagesupply@gmail.com**

**TO: WAYNE DONALDSON
LEDYARD PUBLIC SCHOOLS
4 BLONDERS BLVD.
LEDYARD, CT 06339**

BID #22-2

**ALTERNATE #1 STAGE CURTAINS
\$79,000.00 PER SPECS, SUBSTITUTE ADC TRACK AND LEGS FROM 10' TO 8'
ALTERNATE #1A - \$73,000.00 WITHOUT LINING, MATERIAL IN CRESCENT, ADC
TRACK, LEGS FROM 10' TO 8'**

**ALTERNATE#2 FOLLOWSPOT FIXTURES
\$8,400.00 PER SPECS**

ALL OF THE ABOVE AMOUNTS VALID FOR 90 DAYS FROM BID OPENING.

**FOR FURTHER QUESTIONS, PLEASE DO NOT HESITATE TO CALL OR EMAIL CT.
STAGE
THANK YOU**

to be stained black and sealed 3 times with matt finish sealer. Please provide pricing on the final floor finish to be Rose Brand Stage flooring. Quote Dura Teatro and Glide.

Note: This is a turn Key project, all services needed to provide the school with a 100% functioning audio/theatrical lighting system as depicted in the above pages should be included in vendors pricing.

Makes and model listed were chosen based on the projects budget and needs. Design/functionality deviations will not be permitted.

REFERENCES

List below all requested information for at least five projects. Projects are to be similar in scope of work and contract amount to this project. This reference list must be completed and returned with the Bid proposal.

1. Project Simsbury Name (or
description) Front Curtain + Teasers + Trach Contract
Amount 8500.00 Completion Date 12/15
Owner Simsbury High School
Contact Name Michael Hunter Telephone 860-658-0451
Architect/Consultant none
Contact Name _____ Telephone _____

2. Project Jorgenson Name (or
description) Trach + Curtains Contract
Amount 25,000 Completion Date 2007
Owner UConn
Contact Name Bryam Woscyz Telephone 860-486-1982
Architect/Consultant none
Contact Name _____ Telephone _____

3. Project Name (or Allgrove School
description)
Amount \$5000 Completion Date 2021 Contract
Owner Allgrove School
Contact Name Raymond Engle Telephone 860-653-2505
Architect/Consultant none
Contact Name _____ Telephone _____

4. Project Miss Porters Name _____ (_____ or
description) Curtains Contract
Amount \$3000 Completion Date 2021
Owner Miss Porters School
Contact Name Kate Bradley Telephone 860-306-4689
Architect/Consultant none
Contact Name _____ Telephone _____

Page eleven

Auditorium Sound, Theatrical lighting system completely installed

For the lump sum of \$ _____
Written in words

\$ _____
Written in figures

Alternate #1 Stage Curtain supplied and completely installed

For the lump sum of \$79,000 as spec. substitute ADC Tract +
Written in words less from 10' to 8'

\$ Seventy-nine thousand dollars
Written in figures

Note: Without lining and material in crescent ADC Tract, less from
\$73,000 Seventy Three Thousand dollars 10' to 8'
Alternate #2 followspot fixtures

For the lump sum of 8,400.00
Written in words

\$ Eight thousand, four hundred dollars
Written in Figures

Please note: All of the above amounts
Valid for 90 days from bid opening



358 Sackett Point Road North Haven, Ct 06473
 Phone: (203) 230-0226 Fax: (203) 230-0446
 E-mail: Kurt@soundstagesystems.com

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Date: 3/15/22

Phone:

Location

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Page one

Equipment List

speakers	Auditorium Audio system		
3	JBL full range under balcony speakers	Ac28/26	
2	JBL full range hanging stage speakers	Ac266/99	
9	JBL line array speakers	Vrx932lawh	
3	JBL subwoofer speakers	Vrx 918swh	
2	JBL powered floor monitors	Prx412m	
2	JBL line array hanger bars	Vrxaf	
2	Adaptive line array aiming bars	Sb18	
Microphones			
8	AKG wired vocal microphones	D7	
5	AKG wired overhead microphones	Chm99b	
12	AKG wireless combination microphones	Wms470 vocal set/pt470/c417pp	
3	AKG wireless antenna distributors	Aps4	
8	AKG wired instrument microphones	D40	
Front end			
1	Behringer digital mixing console	X32	
1	Apple 10" tablet	Ipad	
1	Switch craft Bluetooth receiver	318bts	
Processing			
1	BSS digital signal processor	Blue 160 4x12d	

I accept the above Price and Terms:

Signature

Date

Sound Stage System

Date



358 Sackett Point Road North Haven, Ct 06473
 Phone: (203) 230-0226 Fax: (203) 230-0446
 E-mail: Kurt@soundstagesystems.com

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Date: 3/15/22

Phone:

Location

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Page two

Equipment List

Electronics	Auditorium Audio system		
1	AMX touch screen	Md1002	
1	AMX system controller	Nx2200	
3	Crown quad channel power amplifiers	Dci 4/1250	
4	Crown dual channel amplifiers	Dci 4/600	
Video infrastructure			
1	Kramer video mixer	Vs611dt	
1	Kramer receiver for projector	Tp789rxr	
3	Kramer HDMI transmitters stage r/l/booth	Wp211t	
3	Kramer HDMI receivers	Tp789r	
Wall plates			
2	8" x 8" input plates	Per specs	
3	Three gang input/output plates	Per specs	
1	Pit plate	Per specs	

I accept the above Price and Terms:

Signature

Date

Sound Stage System

Date



358 Sackett Point Road North Haven, Ct 06473

Phone: (203) 230-0226 Fax: (203) 230-0446

E-mail: Kurt@soundstagesystems.com

Ledyard High School
24 Gallup Hill Rd
Ledyard, CT

Date: 3/15/22

Phone:

Location

Ledyard High School
24 Gallup Hill Rd
Ledyard, CT

Page four

Equipment List

Power system	Auditorium Theatrical Lighting System	
1	ETC dimming enclosure	Drd6-12-120
1	ETC paradigm termination kit	Pdrd-tk
1	ETC control processor	Pacp3
1	ETC station power module	Pspme
12	ETC dual 20 amp dimmer module	D20
13	ETC dual 20 amp relay module	R20
2	ETC dual 20 amp constant module	Cc20
Architectural controls		
5	ETC preset stations	Uh10005-s4
5	ETC back boxes	Lbb1
5	ETC locking cover	Slc1b
2	ETC LCD touch screen	Pts74
1	ETC backbox	Plcddb
1	ETC locking cover	Plcdlc4
Network control equipment rack		
1	Lowell rack with locking front door	12 space
1	Furman power conditioner	Mx82
1	C2G patch panel	24 port
1	Cable matters cat6 keystone jack	25 pack
1	Lowell cable pass thru	Cbp1
1	Netgear poe switch	Fs728tp
1	Triplite UPS	Smartpro LCD

I accept the above Price and Terms:

Signature

Date

Sound Stage System

Date



358 Sackett Point Road North Haven, Ct 06473
 Phone: (203) 230-0226 Fax: (203) 230-0446
 E-mail: Kurt@soundstagesystems.com

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Date: 3/15/22

Phone:

Location

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Page five

Equipment List

DMX control system	Auditorium Theatrical Lighting System	
1	ETC lighting control console	Element 2 1 k
2	DELL touch monitors 23.8"	P2418ht
1	CBI ethernet extension cable	
7	ETC touring gateways	Rsn dmx 10p4
4	ETC touring gateways	Rsn dmx20p4
7	ETC network plugin stations	Ecpb net
7	ETC back box	Ecpb pb1
7	CBI 10' rh45 extension cables	
Electrical Distribution		
4	SSRC surface mount outlet box	Sm3 2pgfl 1 520d
1	SSRC connector strip	Bal 40-6/12 2 pgpt
3	SSRC connector strip	Bal 40-12/12/ 2pgpt
4	Schedule1 40 1/5" black pipe 42'	
12	Leviton Edison plug	5266-b
48	LED replacement tubes	48"
Stage lighting		
26	ETC color source spot lights	Csspots
26	ETC lens tube	400lt
15	ETC color source pars	Cspar-a
15	ETC wide oval diffuser	Selow 7.5
6	ETC colorsource cyc LED	Cscyc-a
50	CBI dmx m/f extention cables	10'
25	CBI Powercon cables	10'
6	CBI xlr dmx terminator	

I accept the above Price and Terms:

Signature

Date

Sound Stage System

Date



358 Sackett Point Road North Haven, Ct 06473
 Phone: (203) 230-0226 Fax: (203) 230-0446
 E-mail: Kurt@soundstagesystems.com

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Date:

3/15/22

Phone:

Location

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Alternate #1

Equipment List

MAIN VALANCE	Auditorium Stage Drapery		
1	4' x 40' main valance	25 oz prestige	
MAIN TRAVELER			
2	18' X 25' main travelers	25oz prestige	
BOARDERS			
4	4' x 40' boarders	25oz prestige	
LEGS			
8	18' x 10' legs	25oz prestige	
US TRAVELER			
2	18' x 25' US travelers	23 oz drama	
CYCLORAMA			
1	16' x 48' white muslin	IFR	
DRAPERY RIGGING			
13	Schedule 40 1.5" black batten pipe 42'		
97	Beam clamp rigging points	P305	
DRAPERY TRACK			
2	iWeiss bi-parting track 52'	cwana	
1	iWeiss walk long track 50'	Cwana	
8	iWeiss walk along track 10'	Cwana	

I accept the above Price and Terms:

Signature

Date

Sound Stage System

Date

Date _____



358 Sackett Point Road North Haven, Ct 06473
 Phone: (203) 230-0226 Fax: (203) 230-0446
 E-mail: Kurt@soundstagesystems.com

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Date: 3/15/22

Phone:

Location

Ledyard High School
 24 Gallup Hill Rd
 Ledyard, CT

Alternate # 5 Equipment List

Auditorium Stage Flooring			
Hardwood			
2100 sqft +/-	¾" solid red oak flooring tongue/grove		
2100 sqft +/-	4'x8' plywood sub floor		
All needed	Adhesive/fasteners		
1 coat	Black stain		
3 coats	Matt finish poly sealer		
Rose brand Dura			
2100 sqft +/-	Dura flooring		
2100 sqft +/-	4'x8' plywood sub floor		
All needed	Adhesives/fasteners		
Rose Brand Teatro			
2100 sqft +/-	Teatra flooring		
2100 sqft +/-	4' x8' plywood flooring		
All needed	Adhesives/fasteners		
Rose Brand Glide			
2100 sqft +/-	Glide Flooring		
2100 sqft +/-	4' x8' plywood flooring		
All needed	Adhesives/fasteners		

I accept the above Price and Terms:

Signature

Date

Sound Stage System

Date

REFERENCES

List below all requested information for at least five projects. Projects are to be similar in scope of work and contract amount to this project. This reference list must be completed and returned with the bid proposal.

1. Project Name (or description)

Sacred Heart Theater
Contract Amount \$400,000 - Completion Date 12/21
Owner Sacred Heart University
Contact Name Jason Ebert Telephone 203 915 5948
Architect/Consultant Design/Build
Contact Name Kurt Kieslich Telephone 203 230 0226

2. Project Name (or description)

Wallingford Schools Auditoriums (4 schools)
Contract Amount \$850,000 - Completion Date 2019
Owner Town of Wallingford
Contact Name Adam Annilli Telephone 860 644 2427
Architect/Consultant Theater Projects
Contact Name Jim Niesel Telephone 203 299 0830 Ext 270

3. Project Name (or description)

Southington High School
Contract Amount \$150,000 - Completion Date 2021
Owner Town of Southington
Contact Name Jennifer Mellit Telephone 860 628 3200 Ext 10212
Architect/Consultant Design/Build
Contact Name Kurt Kieslich Telephone 203 230 0226

4. Project Name (or description)

Rippowam Middle School

Contract Amount \$700,000 - Completion Date 2022

Owner Town of Stamford

Contact Name Mike Skapczynski Telephone 860 496 4226

Architect/Consultant BBS Architects

Contact Name Doug Glass Telephone 631 475 0349

5. Project Name (or description)

North Haven High School

Contract Amount \$100,000 - Completion Date 2020

Owner Town of North Haven

Contact Name Phil Diaw Telephone 203 804 8832

Architect/Consultant Design/Build

Contact Name Kurt Rieslich Telephone 203 230 0226

Auditorium Sound, Theatrical lighting system completely installed

For the lump sum of Three hundred forty two thousand nine hundred four dollars
(Written in words) 00

\$342,904
(Written in figures)

Alternate #1 Stage Curtain supplied and completely installed

For the lump sum of Eighty nine thousand six hundred eight three
(Written in words) 00 dollars

\$89,683
(Written in figures)

Alternate # 2 followspot fixtures

For the lump sum of Nine thousand dollars — 00/100
(Written in words)

\$ 9000⁰⁰ —
(Written in figures)

Alternate # 3 Moving yoke fixtures

For the lump sum of Thirty one thousand five hundred dollars 00/100
(Written in words)

\$ 31,500⁰⁰ —
(Written in figures)

Alternate #4 wireless control of lighting

For the lump sum of Twenty four hundred fifty dollars 00/100
(Written in words)

\$ 2450⁰⁰ —
(Written in figures)

Alternate #5 Stage floor replacement

For the lump sum of fifty eight thousand six hundred ninety one 00/100
(Written in words)

\$ 58,691⁰⁰ —
(Written in figures)

Rose Brand Flooring Dura

For the lump sum of Forty two thousand six hundred fifty two 00/100
(Written in words)

\$ 42,652⁰⁰ —
(Written in figures)

Rose Brand Flooring Teatro

For the lump sum of Forty three thousand four hundred eleven ⁰⁰/₁₀₀
(Written in words)

\$ 43,411 ⁰⁰-

(Written in figures)

Rose Brand Flooring Glide

For the lump sum of Forty three thousand six hundred sixty seven ⁰⁰/₁₀₀
(Written in words)

\$ 43,667 ⁰⁰-

(Written in figures)